



ECS Southeast, LLP

1281 Kennestone Circle NE
Suite 200
Marietta, GA 30066
(770) 590-1971 [Phone]
(770) 590-1975 [Fax]

LETTER OF TRANSMITTAL

June 1, 2017

Clark Patterson Lee
3011 Sutton Gate Drive
Suite 130
Suwanee, GA 30024

ATTN: Mr. Rich Edinger, P.E.

RE: **Avondale Estates - Coring**

ECS Job # **10:9517**

Permits:

Location: **Various Roads
Avondale Estates, GA**

We are enclosing:

- Materials Engineering Division Reports
- For your use
- As requested

ENCL:

Field Report # 2 06/01/2017

Doug Coffey, P.E.
Construction Material Department Manager

Mel Christian
Senior Project Manager



ECS Southeast, LLP

1281 Kennestone Circle NE
 Suite 200
 Marietta, GA 30066
 (770) 590-1971 [Phone]
 (770) 590-1975 [Fax]

FIELD REPORT

Project **Avondale Estates - Coring**
 Location **Avondale Estates, GA**
 Client **Clark Patterson Lee - Rich Edinger, P.E.**

Project No. **10:9517**
 Report No. **2**
 Day & Date **Thursday 06/01/2017**
 Weather
 On-Site Time **0.00**
 Lab Time **0.00**
 Travel Time* **0.00**
 Total **0.00**
 Re Obs.Time **0.00**

Remarks

Trip Charges*	Tolls/Parking*	Mileage*	Time of Arrival	Departure
			08:00A	08:00A
Chargeable Items				

* Travel time and mileage will be billed in accordance with the contract.

Summary of Services Performed (field test data, locations, elevations & depths are estimates) & Individuals Contacted.

A total of 14 Asphalt cores were obtained on 5-17-17 from the road sections listed below. The samples were delivered to our laboratory to determine the in-place thickness of the existing asphalt. 2 cores were taken from each road section.

Locations and results of the total asphalt thickness are as follows:

- Charlbury Pl. from Clarendon Ave to Chatsworth Dr.= 5.40" and 4.60"
- Laredo Dr. from N. Clarendon Ave to CSX RR Tracks = 7.40" and 5.60"
- Stratford Green Ct. from Stratford Green to End = 2.60" and 2.80"
- Stratford Green Pl. from Stratford Green to End = 2.40" and 4.60"
- Stratford Green Way from Stratford Green to Stratford Green = 2.90" and 2.50"
- Stratford Rd. from Covington Hwy to Kensington Rd = 7.20" and 7.90"
- Stratford Rd. from Kensington Rd. to Wiltshire Dr.= 5.00" and 3.70"